# **Designer Collection** Tubs






50" x 23.625" / 34.75" x 23.75"

**DROP-IN or UNDERMOUNT** Not recommended as a tub/shower combination 71 gal to overflow

Acrylic CXL<sup>™</sup>

100 lbs / 45 kg soaker 150 lbs / 68 kg plumbed


Filling this tub to the maximum may require an above average size or dedicated water heater.



#### PLEASE NOTE:

This tub is very small and is intended for applications where space is extremely limited.

Numbered areas on tub deck represent possible locations to install cleaning systems, faucets and other fixtures. Pump extends 6"-7" beyond edge of tub. Shown with Air Massage and Standard Whirlpool Package.



#### **IMPORTANT:** Air baths and tubs with a pre-leveled foam base or frame system add 2-3" to overall tub height.

### **IMPORTANT ORDERING & INSTALLATION INFORMATION**

- Before ordering or installing, please consider future access to equipment.
- · Add proper bedding compound to fully level and support bottom of tub.
- · When equipped with an air bath package, pre-leveled foam base or frame system, overall tub height is increased by approx. 2-3" and is designed to install on a flat, level subfloor.

0

-

- · Radiance placed on airbath floor will affect placement of air jets.
- · System components may extend beyond the perimeter of deck.

- Measure tub on-site before building tub decking.
  - · Advise MTI when planning to use a glass enclosure. Relocation of controls may be necessary.
  - · Suction and control locations may vary.
  - · System components may extend beyond the perimeter of deck.
  - All tubs are compliant with ASTM C 1028-07 coefficient of friction. DoloMatte meets ANSI A137.1/A326.3 coefficient of friction and AS HB198:2014 slip tests.

### **ELECTRICAL COMPONENTS & SPECIFICATIONS**

Hydrotherapy Package	Components Included	GFCI / 110V
Standard Whirlpool	2-bhp pump	1-15 amp
Microbubbles	Microbubbles pump	1-15 amp
Air Massage	heated blower	1-15 amp
Air Massage Elite	heated blower, chromatherapy	1-15 amp
Electrical requirements may change with the addition of optional therapy components. See specific option details or installation information.		

CSA Certified C/US; B45.5/IAPMO ANSI Z124.1 and ANSI 112.19.7

Hydrotherapy Package Components Included GFCI / 110V Microbubbles with Air Microbubbles pump, heated blower 1-20 amp Microbubbles with Air Flite Microbubbles pump, heated blower, chromatherapy 2-15 amp Air with Whirlpool 2-15 amp 2-bhp pump, heated blower Air Elite with Whirlpool 2-bhp pump, heated blower, chromatherapy 2-15 amp

e the Installation & Operation Manual for more details

MTI's Customer Service Monday-Friday 8am-6pm EST

800-783-8827 or service@mtibaths.com

Before discarding tub crate, check for accessories that may be packaged inside

- All product measurements are 1/12".
  Specifications and configurations are subject to change without notice.
  Measurements herein supersede all others published prior to publication date below.



# Atlantica MODEL # 65 50" x 23.625" / 34.75" x 23.75"

- Aromatherapy is eliminated for undermount applications
- Air Baths, Pre-Leveled Foam Base or Frame Systems
- increase overall height by 2-3".

Hydrotherapy Packages	Package Contents	Part #	MSRP
Soaker	Soaking bath - no jets	S65-DI	\$3,415
		S65-UM	
Microbubbles	1 microbubbles infusion port and pump	M65-DI	\$6,735
		M65-UM	
Air Massage	20 air jets, heated air blower, pre-leveled foam base	AST65-DI	\$7,065
		AST65-UM	
Air Massage Elite	30 air jets, heated air blower, Chromatherapy LED lighting, Spa Mode, pre-leveled foam base	AE65-DI	\$8,965
		AE65-UM	
Microbubbles with Air Massage	1 microbubbles infusion port and pump, 20 air jets, heated air blower, pre-leveled foam base	ASTM65-DI	\$9,785
		ASTM65-UM	
Microbubbles with Air Massage Elite	1 microbubbles infusion port and pump, 30 air jets, heated air blower, Chromatherapy LED lighting, Spa Mode, pre-leveled foam base	AEM65-DI	\$11,585
		AEM65-UM	
Standard Whirlpool	6 point-massage jets, 2-bhp pump	P65-DI	\$6,270
		P65-UM	
Air Massage with Standard Whirlpool	6 point-massage jets, 2-bhp pump, 20 air jets, heated air blower, pre-leveled foam base	AW65-DI	±0.000
		AW65-UM	\$9,920
Air Massage Elite with Standard Whirlpool	6 point-massage jets, 2-bhp pump, 30 air jets, heated air blower, Chromatherapy LED lighting, Spa Mode, pre-leveled foam base	AEAP65-DI	\$11,820
		AEAP65-UM	

**RECOMMENDED SENSORY THERAPIES** 

#### Audiotherapy

(LE) **\$800** underwater lighting *2 LED lights included* 

Chromatherapy

# (STEREOBT) **\$1,390** 2 transducers with bluetooth and amplifier (BTREMOTE) **\$600** bluetooth remote

(STEREOH202) **\$1,575** 4 transducers *amplifier not included* 

# Thermaltherapy

(RAD100) **\$1,595** Radiance® 2 heated zones included (HTISOAK) **\$825** 



For more information on options and accessories go to Acrylic Tub Options on mtibaths.com

# Atlantica MODEL # 65

**Options** Must be ordered at time of purchase.

Standard Colors White (CWH) only

Quick Ship reduces lead time (QSPRI) \$430 Please call for availability

Inline Heater maintains water temperature For Soaker or Air Baths (HTISOAK) **\$825** Includes a recirculating pump Cannot be combined with Microbubbles.

Virtual Spout high-flow integrated tub filler (FPMJ) **\$450** Must specify stub-out location on order. See page 1 for location options.

Grab Bars from \$330 Selections vary. Personalization available.

**Textured, Slip-Resistant Bottom** (TXTBTM) **\$105** Compliant with ASTM C 1028-07 friction coefficient.

## Accessories

Pillows from \$180

Teak Bath Mat (TKMAT3018) **\$815** Custom sizes also available. Contact MTI for details and pricing.

# Installation Options Must be ordered at time of purchase.

Pre-Leveled Foam Base (PLFOAM) \$295 All airbaths include a pre-leveled foam base. Pre-Leveled Frame and Foam Base (PLF) \$740 Pre-Leveled Frame and Foam Base with Skirting For pricing and details go to mtibaths.com

## **Drains & Overflow Kits**

### Cable Driven

Drain Finishes – PVC Drain Kit White/Bone/Biscuit (WOCDW) \$440 Chrome (WOCD) \$410 Brushed Nickel (WOCDBN) \$490 Polished Nickel (WOCDBN) \$540 Oil-Rubbed Bronze<sup>+</sup> (WOCDOR) \$550 Polished Brass (WOCDBR) \$690 Special Finishes\* (WOCDSF) \$1,135

MTI does not offer a brass body cable drain kit.

Lift & Turn

Drain Finishes – PVC Drain Kit Chrome (WOC) **\$185** White (WOW) **\$245** Brushed Nickel (WOBN) **\$305** 

l	Hydrotherapy Equipment & Cleaning Systems Must be ordered at time of purchase.
	Inline Heater maintains water temperature For Whirlpools or Stream Bath (HTI) <b>\$570</b> Uses existing pump Cannot be combined with Microbubbles.
	Whirlpool Cleaning Systems      Fill-Flush (FFSO) \$590      Simple Touch (FFE) \$1,020      Must specify stub-out location on order. See page 1 for location options.
_	Whirlpool Jets    Pump upgrade may be advisable for optimal performance when adding jets.      Point-Massage Jet    Extra Point-Massage Jet (EJ) \$315      Micro-Jet from \$360    Jet styles and packages vary. Personalization available.      Pump Upgrade - 3-bhp    (PUMP3) \$315
	Jet Trim Kits For Standard Whirlpool Chrome (TRC) <b>\$270</b> , Brushed Nickel (TRBN) <b>\$725</b> For Ultra Whirlpool Chrome (TRCU) <b>\$370</b> , Brushed Nickel (TRBNU) <b>\$960</b>
_	Ozonator (OZONE) \$515

## Tile Flange

Factory-Installed on 3 sides - rigid ABS (TFK3) **\$200** Field Install Kit - includes rigid ABS & adhesive (TFKNI) **\$185** IMPORTANT: Must specify flange location(s) on order of Factory-Installed Flange. Not available with optional Low-Profile Rim.

Cannot be added to soakers or airbaths without combination hydrotherapy package or HTISOAK.

#### Toe Tap

Round Overflow – PVC Drain Kit Chrome (WOTTC) \$380 Brushed Nickel (WOTTBN) \$385 Polished Nickel (WOTTPN) \$385 Special Finishes\* (WOTTSF) \$1,145 Round Overflow – Solid Brass Drain Chrome (WOTTSBC) \$810 Brushed Nickel (WOTTSBBN) \$810 Polished Nickel (WOTTSBPN) \$810

