## NAMEEK'S

Remer SFR7192 Shower Faucet

#### Features

- Solid brass rough-in valve included.
- 6" rain shower head.
- 2-way concealed diverter (2 water outlets).
- Pressure balance cartridge.
- Ceramic disc technology.
- 4-function hand shower.
- 27" sliding rail included.
- 1/2" NPT inlets and outlets (compatible with US plumbing connections)

#### Installation

• Wall mounted installation.

#### **Included Pieces**


- Shower arm with flange. (Remer 342US-CR)
- 6" rain shower head. (Remer 354PL)
- 2-way shower diverter with rough-in valve. (Remer J09-CR)
- Hand shower. (Remer 318DK)
- Flexible shower hose. (Remer 333CNX150-CR)
- Water connection. (Remer 309LUS-CR)
- 27" sliding rail bracket. (Remer 315R)



### Nameek's One-Year Limited Warranty

See website for warranty information details.

#### **Color/Finish Details**











### **Shower Arm**

Remer 342US-CR



### **Rain Shower Head**

Remer 354PL



USA/Canada: 215.256.4197 Nameek's reserves the right to make revisions without notice to product specifications. For more information, go to www.nameeks.com






Remer SFR7192 Shower Faucet

### Shower Valve (Trim + Rough-in Valve)

Remer J09-CR



USA/Canada: 215.256.4197 Nameek's reserves the right to make revisions without notice to product specifications. For more information, go to www.nameeks.com








### Hand Shower

Remer 318DK










# Sliding Rail Remer 315R










### Water Connection


Remer 309LUS-CR



G 1/2"

### **Shower Hose**

Remer 333CNX150-CR



NAMEEK'S





#### **Technical Information**

Shower head size:	6.30"
Shower head type:	Rain
Pivoting shower head:	Yes
Shower arm length:	5.12"
Rough-in included:	Yes
Material:	Brass ABS
Cartridge type:	Pressure balance Ceramic disc technology
Hand shower functions:	Wide Massage Vigorous Aerated spray

#### Notes

This item is recommended to be installed by a licensed plumber or professional only. Please ensure to observe all local and building code requirements. Shut off water supply prior to installation.

Includes mounting hardware.

